

Wheels: An e-mail from Galen says, “I’ve got a 1989 Chevrolet step-side truck. When I stop there is a thud in the rear end and then it does it again when I take off. I have checked everything and need HELP.”

Halderman: This is a common problem and it is usually due to lack of grease in the splines of the driveshaft. The driveshaft has to be removed and then a high-temperature grease applied to the splines and reinstalled.

